



ལྷན་ཡོད་སྒོ་སྤོང་སྤྱི་ལཱ་ལོ་གསལ་དང་འཇོ་རྟེན་མ་དངུལ།

NATIONAL PENSION AND PROVIDENT FUND

Securing Future Together

NPPF/ROP-07/2022-2023/30

Date: 06/09/2022

To,
The Bidding Contractors
Bhutan,

Sub: Addendum

This is with reference to our Notice Inviting Tender vide NPPF/ROP-07/2022-2023/20 20th August 2022 for the Road Resurfacing in NPPF Residential Complex in Phuentsholing, you are requested to note the below mentioned amendment in the Bidding Documents. Please fill in the rates in the enclosed BOQ of new item "Access Road" numbered 4.A to 4.E and which is not included in the tender document for the particular item.

Item no.	Ref.Code BSR 2022	Description	Quantity	Unit	Rate	Amount (Nu.)
4.A	DD0001	Demolishing cement concrete 1:3:6 & richer, including disposal of materials within 50m lead: Underground water tank 3x4m	2.80	Sq.m		
4.B	CG0002	Clearing jungle including uprooting of vegetation & trees of girth < 300mm & disposal within 500m of the site	285.40	Sq.m		
4.C.1	EW0021	Earth work in surface excavation, depth 1.5m, area >10 Sq.m in plan, including disposal of excavated earth within 50m lead & 1.5m lift and disposed soil to be neatly dressed-All types of soil	145.00	Sq.m		
4.C.2	EW0031	Earth work in excavation over areas, depth >300mm, width >1.5m, area >10 Sq.m on plan, including leveling, dressing, ramming & refilling, disposal of surplus soil within 50m lead & 1.5m lift-All type of soil, rock. Underground service cables and pipes should be taken care of during execution of the work.	140.40	Sq.m		
4.C.3	EW0196	Providing & laying sand & gravel (<i>river bajree</i>), including leveling, watering, ramming, dressing	22.85	Cu.m		
4.D.1	SM0072	Providing and laying Hand packed stone filling or soling with stones	0.25	Cu.m		
4.D.2	CW0005	Providing and laying in position plain cement concrete excluding the cost of centering and shuttering - 1:3:6 (1 cement: 3 sand: 6 graded crushed rock 20 mm nominal size).	0.25	Cu.m		
4.D.3	SM0006	Providing & laying Random Rubble Masonry with hard stone in foundation & plinth-In cement mortar 1:5	4	Cu.m		
4.D.4	CW0071	Providing and fixing pre-cast cement concrete solid block including hoisting and setting in position with cement mortar 1:3 (1 cement : 3 sand) including the cost of required formwork and finishing smooth with 6 mm thick cement plaster on exposed surface complete-two 2.5x1m slab	1	Cu.m		



ཀྲུལ་ཡོངས་དགོངས་ཁྲིའི་ཟུར་ཕོགས་དང་འཇོ་རྟེན་མ་དངུལ།།

NATIONAL PENSION AND PROVIDENT FUND

Securing Future Together

4.E	RC0083	Providing & fixing Thermo-Mechanically Treated reinforcement bar (Yield strength 500 MPa) for RCC work including cutting, bending and placing in position complete-2 slabs of dim 1x2.5x0.2 m with rebar 16mmø @100 c/c	146.94	kg		
Total of Access Road						

Yours Faithfully



Regional Head
NPPF, Phuentsholing